

# Open Housing Our Perspective

Corey Bosko  
BSc, P. Ag  
Production Manager and Compliance Specialist



## The Progressive Group

~45,000 sows under our "umbrella" - farrow to iso-wean

- Export market
- Nursery and finishing spaces
- Valley Lee Berkshire

Provide services including production advice, business support and marketing.



- ▶ Gestal - 8 farms
  - ▶ 3 Prop-12 farms
- ▶ Maximus - 2 farms
- ▶ Shoulder Stalls - 2 farms
- ▶ 6 more farms to convert



**THE**  
*Progressive*  
**Group**  
OF COMPANIES, INC.



# The Inevitable Transition

**THE**  
*Progressive*  
**Group**  
OF COMPANIES, INC.

## Conversions - Things to Consider

- ▶ Existing Structures
  - ▶ Assess Infrastructure
- ▶ ESF or Shoulder Stalls?
- ▶ Current Footprint or Expand?
- ▶ Herd Size
- ▶ Ventilation
- ▶ Flooring
- ▶ Pen Layouts
- ▶ Dunging Patterns
- ▶ Water Supply and Placement

## Types of Conversions

New Build

Current Footprint  
(moved animals off  
site and converted)

Expansion/Conversion

Prop 12

## New Build

### Turned misfortune into opportunity

- Fully slatted
- Designed from scratch
- Did keep a portion of population off-site
  - “If we did it again, would have done complete depop”



## New Build

- ▶ Maximus system
  - ▶ Farrowing and open housing
- ▶ Geothermal heating
- ▶ Training sows
- ▶ Training staff
- ▶ Integrated data
- ▶ Underground plenum for cooling
- ▶ Some mechanical issues
- ▶ Water build up an issue



# Current Footprint

Animals Stay On-site  
Shoulder Stall Conversion



## Current Footprint

Animals Moved Off-Site and Converted

- ▶ finisher barn training barn
- ▶ Bred and preg-checked in main farm
- ▶ Moved sows between 30 and 60 days pregnant to off-site conversion
- ▶ 3 X 3000 sow continuous flow farms done this way

## Current Footprint

- ▶ Gutted and renovated breeding rooms in a 40-day time frame to bring back sows prior to farrowing (100 days gestation).
  - ▶ 4 batches of sows (4 rooms)
  - ▶ 644 sows (4 trucks)
  - ▶ All trained in finisher site
  - ▶ Brought back to main farm to farrow

1	2
3	4



## Current Footprint (moved animals off-site and converted)

- ▶ Positives
  - ▶ Inventory stable
  - ▶ Production continues
  - ▶ Wide open rooms for ease of conversion/biosecurity





## Current Footprint (moved animals off-site and converted)

### ► Negatives

- Timeline is very important (no room for error or delays)
- Some pregnancy losses due to transport and stress
- Biosecurity risk with transport
- Training 644 sows all at the same time
- Cost of finisher barn conversion and transport



## Expansion/Conversion

- 2 X 600-sow Farrow to Finish Expansion/Conversions
- 3000-sow to a 5000-sow Farrow to Iso-wean Expansion
- 1700-sow (multi-site production to a 1-site production) Expansion

## 600 Sow Farrow to Finish to 2500 sow Farrow to Iso-Wean (2 farms)



- ▶ Added farrowing space
- ▶ Converted Grower and Finisher Rooms
- ▶ Gradual Conversion
- ▶ Increased Sow Inventory Over Time
  - ▶ Continuous Flow to 4-week batch
  - ▶ 4-week batch converted to 2-week batch



## New Farrowing





## ► Positives

- Able to increase inventory for better contract negotiations
- Great flooring
- Herd stability
- No shipping
- Gradual training



**THE**  
**Progressive**  
**Group**  
OF COMPANIES INC.

## ► Negatives:

- Over-ventilated for reduced number of animals
- Construction delays and production delays can cause time constraints with emptying grow/finish rooms/converting rooms and loading pregnant sows into renovated spaces

**(GIVE YOURSELF A BUFFER)**



**THE**  
**Progressive**  
**Group**  
OF COMPANIES INC.






## Expansion/Conversion

Expanded current footprint

- ▶ Fully slatted open housing/freedom stall breeding
- ▶ Additional farrowing space





#### ► Positives:

- Ventilation designed for open housing
- Clean and easy to manage
- Allows for timeline delays/issues
- Small groups of animals being trained at one time
- Proper slats/slat width for sow health and welfare

## Expansion/Conversion

**Progressive**  
Group  
OF COMPANIES INC.

## Expansion/Conversion

#### Negatives

- Converting partial rooms of breeding crates tricky for biosecurity
- Slat width usually not correct for walking on continuously/sow fighting
- Disruptive for production flow and logistics
- Fully slatted flooring harder to back-feed in the event of health challenges



**Progressive**  
Group  
OF COMPANIES INC.



## Expansion/Conversion

- ▶ Converted some breeding crates to open housing to minimize requirement of extra square footage (cost)
  - ▶ Some solid sections (hallways and solid areas of removed breeding crates)
  - ▶ Ventilation not designed for proper dunging patterns leads to messy pens and extra scraping
- ▶ Easier for back-feeding

**Progressive**  
**Group**  
OF COMPANIES INC.

## Electronic Sow Feeding Versus Shoulder Stalls

**Progressive**  
**Group**  
OF COMPANIES INC.

# Electronic Feeding Stations



## When it works, its great

Uniform Body Conditions  
Targeted feeding  
Customizable feed curves  
The system will feed her no matter what as long as...



## Technology

Station goes down/stocking density  
Communication disruptions  
"bugs"  
Tags



## People

Stockmanship combined with understanding the technology a must  
It's not a set it and forget it system



# Shoulder Stalls

- ▶ Cut off the back 2/3 of current gestation crate and create a pen containing 11 - 24 sows
- ▶ Leave slatted "back area" as a loose pen for the sows
- ▶ Anchored the front part of the crates down
  - ▶ Solid flooring versus slats







## Shoulder Stalls

### ► Positives


- Cost and time benefits
- Troughs stay in place
- Current feed system stays in place
- No training (animals and people)
- No tags required
- Ability to back-feed pre-farrow



## Shoulder Stalls

### ► Negatives

- Body condition variability
- Bully sows
- Square footage/space allowance
- Anchoring
  - Solid versus slatted flooring
- Dead stock removal
- Maintenance



## Proposition 12 - 3 sites

- ▶ 2 sites - built brand new freedom stall area
  - ▶ Proper slats
  - ▶ Brand new crates
  - ▶ Works very well

**Progressive**  
**Group**  
OF COMPANIES INC.

## Proposition 12 - 3 sites



- ▶ 1 site converted old breeding into freedom stalls
  - ▶ Removed row of stalls to create "pen"
  - ▶ Slats not ideal, solid flooring not ideal
    - ▶ Issues with lameness due to fighting
  - ▶ Works ok

**Progressive**  
**Group**  
OF COMPANIES INC.





## Water Line Placement

- ▶ Pit charging is essential to keep down gases
- ▶ Water line placement is important for adding water to pits as well as keeping solid areas dry



## Converting Can Be Scary!!

- ▶ Be informed
- ▶ Do your homework
- ▶ Plan
- ▶ Give yourself time
- ▶ Try to have all construction materials on site



A grayscale photograph of several pigs resting in a farm enclosure with metal railings. A large green geometric overlay is on the right side of the image.

Thank You!

THE  
**Progressive**  
**Group** OF COMPANIES, INC.